

BELVIDERE & DELAWARE RIVER RAILWAY

RFP 1701 ADDENDUM 1.

1. This Addendum is attached to, and made a part of, this Railroad's RFP 1701 and Schedule A. All proposals shall make note of this Addendum.
2. Clean **1-1/2"** (not 2-1/2") hard rock ballast shall be provided, tamped, regulated, and broomed, to support a uniform line and surface, and to fill all cribs, and provide uniform shoulders, throughout the project limits, with run offs as required to existing track.
3. At, or near the end of the project, all track joint bolts shall be tightened by mechanical means, and missing or broken bolts shall be replaced with new bolts, nuts, and washers, of the proper size, which shall also be tightened by mechanical means.
4. As part of the Proposal, Contractors shall provide a letter from the Federal Railroad Administration stating that the Contractor has an approved Control of Drug and Alcohol Program on file with the FRA.

K.BURENGA

President & General Manager

Phone 833-752-1849 Extension 704

Email: KBurenga@BRWRR.com

Fax 908-782-0134

**THERE IS NO JOB SO IMPORTANT, NO SERVICE SO URGENT,
THAT IT NEEDS TO BE DONE, EXCEPT SAFELY.**